

# ULK TELESCOPIC LIFTING TOWERS (FRONT-LOADER)



Fitted with 4 stabiliser braces for greater lift stability.



Auto-brake Winch  
Complies with CE Machinery Directives.




Automatic Safety Blocking System (ASB)



Internal Pendulum Brake System (IPB)



7x19+0



Reinforced Aluminium masts (EN-AW 6082 T6). Galvanised steel wire rope. Stainless steel magnetic fastener bolts (Neodymium).



4 wheels (Ø100mm) with steel fastening plates secured by 4 bolts each. Base fitted with spirit level.



Mast Section Unlocking System (MSU)



Leveller screw jacks with double thread for a quick adjustment. Chrome foot plates with non-slip injection moulded rubber pads..




2 heavy-duty Ø150mm wheels for horizontal transportation & loading into vehicles.



U-shaped steel plate to reinforce the securing of the mast sections to the base. Integrated manual holder.



Mast Sequence Control System (MSC)



More mast overlap. Prevent fishing rod effect.



Cable resend system with steel pulleys.



Fold-away handles with 2 heavy-duty Ø150 mm wheels for horizontal transportation & loading into vehicles.



60x60mm Reinforced forks. Fork carriage with 2 positions. Adjustable & detachable design.